

OSO-TRABUCO STRUCTURAL REINFORCEMENT FOR RAILROAD EXPANSION



Oso-Trabuco Bypass Set-up



Re-coating of Existing Manhole



Crews Pour New Pad at Existing Manhole

PROJECT LOCATION:

San Juan Capistrano

PROJECT SCOPE:

Orange County Transportation Authority (OCTA) will be constructing a passing siding track parallel to the existing main track between Camino Capistrano and Oso Creek in the area of Saddleback Church Rancho Capistrano in the City of San Juan Capistrano. In some locations, the new passing siding track will be located in closer proximity to the Oso-Trabuco pipeline. It was recommended to reinforce our pipeline using Cured-In-Place-Pipe (CIPP).

The work for this project includes approximately 1,500 feet of Cured In Place Pipe lining, manhole rehabilitation, and a temporary sewer bypass system.

Construction documents for the Oso-Trabuco Structural Reinforcement for Railroad Expansion project were prepared by AKM Consulting Engineers.

PROJECT DETAILS:

- Contract Award - 10/18/2018
- Construction Contract - \$1,173,000
- Percentage Constructed - 100%
- Completed - January 2019

NOTES:

Construction completed mid-January.