

EMERGENCY GENERATOR



Existing Emergency Generator

PROJECT LOCATION:

Laguna Hills

PROJECT SCOPE:

The proposed Emergency Generator consists of a new 1-Megawatt diesel engine driven generator, particulate filter assembly, exhaust silencer assembly, diesel storage tank, concrete masonry unit building structure, acoustic paneling, and louvers. The generator will support the District's operations by providing electrical power to all Plant 2A facilities in the event of a loss of utility power in emergencies or during planned outages. This new generator is necessary to support District facilities in its function as a 24-hour emergency operations center.

Construction documents for the project were prepared by Ware Malcomb.

PROJECT DETAILS:

- Contract Award - 05/23/2019
- Construction Contract - \$1,314,063
- Percentage Constructed - 0%
- Estimated Completion - February 2021

NOTES:

Notice to proceed issued 5/29/19. Mobilization scheduled to begin 8/26/19.