

MNWD Construction Notes

(rev May 2014)

These construction notes must appear on the notes sheet of every plan sheet submitted for District's review and approval:

MNWD construction notes:

1. The Moulton Niguel Water District inspector shall be notified at least two (2) working days prior to beginning of construction. Call (949) 425-3530 to arrange for inspection.
2. A preconstruction conference of representatives from applicable agencies shall be held on site at least one (1) week prior to beginning construction at which time construction schedule and 24-hour contact information shall be provided to MNWD.
3. Contractor shall maintain access to the site at all times for Moulton Niguel Water District personnel. Open trenches shall be properly plated at the end of each working day to allow for 24-hour MNWD access to the site.
4. The Contractor and Cell Carrier shall be responsible for any damage due to construction activities to the existing site and shall return damaged facilities to existing condition or better at no cost to the District.
5. The Contractor shall notify underground service alert (DIG ALERT) at least two (2) working days prior to beginning construction at 1-800-422-4133. Any MNWD facilities to be crossed or paralleled within five feet shall be potholed to verify location prior to working in the vicinity of MNWD facilities.
6. The Contractor shall contact the District coating representative Harper Engineering for coating requirements and inspections at (951) 372-9196 prior to any work on a steel tank. Harper Engineering shall be present during preconstruction conference.
7. All new and existing facilities owned by the represented cellular carrier shall be properly tagged identifying the owner's name and 24-hour phone number.
8. The Contractor shall have a copy of plans approved by the MNWD Director of Engineering and Operation and a Consent Letter on-site at all times.
9. The Contractor is responsible to ensure the site is secure at all times, during both working and non-working hours.
10. The Contractor shall provide the District with two (2) sets of approved construction plans prior to scheduling inspection, and submit as-built drawings to the District upon completion of the job.
11. The contractor shall sawcut all pavements. Backfill shall be one sack slurry or aggregate base to within 1" of existing AC.
12. The contractor shall provide a minimum cover of 30-inches on top of all conduits.
13. The contractor shall replace asphalt pavement with: 1st lift - 3/4" mix, relative compaction 95%, no more than 3" placed at any one time. 2nd lift - 1/2" fine, no more than 1 1/2" lift.
14. The contractor shall slurry seal the entire work area and any damaged areas curb to curb. The contractor may be required to slurry seal additional areas as required by District inspector.
14B. If applicable, see Section 2.7 of MNWD Policy & Procedures, Softscape Replacement.
15. The contractor and license holder shall perform a final walkthrough for release.